

**Funds Acquisition Form  
2013-2015 State Capital Budget  
Chehalis River Basin**

Return to: Scott Boettcher ([scottb@sbgh-partners.com](mailto:scottb@sbgh-partners.com))

PROJECT NAME	
<b>Pe Ell Wastewater Treatment Plant Flood Prevention Dike</b>	
Date:	8/6/13
Funds requested:	\$521,000
Project sponsor:	Town of Pe Ell
Project contact:	Spencer Nichols, Mayor 111 S Main St PO Box 215 Pe Ell, WA 98572 <a href="mailto:peellmayor@centurytel.net">peellmayor@centurytel.net</a> 360/291-3543 360/324-2132 (cell)
Project description, including project phases:	The proposed project will design and construct approximately 900 linear feet of dike along the northwest side of the WWTP to protect the WWTP from flood events. The top of the dike will have an elevation of approximately 365.00 feet, which is approximately 2 feet higher than the water level reached in the 2007 flood event.
Scope of work showing timeline, expenditure plan and deliverables:	<p>Task 1 – Complete Final Engineering Design</p> <p>Start Date: September 2013</p> <p>Completion Date: December 2013</p> <p>Estimated Cost: \$52,600</p> <p>Deliverables: Plans, Specifications, and Cost Estimate</p> <p>Task 2 – Complete Environmental Review and Obtain Permits</p> <p>Start Date: November 2013</p> <p>Completion Date: February 2014</p> <p>Estimated Cost: \$2,500</p> <p>Deliverables: SEPA, Shoreline Permit, Critical Area Permit, Fill and Grade Permit</p> <p>Task 3 – Construct Dike</p> <p>Start Date: May 2014</p> <p>Completion Date: July 2014</p> <p>Estimated Cost: \$465,900</p> <p>Deliverables: Completed WWTP Dike</p>
Description and timing of flood hazard reduction benefit(s) to be achieved:	The WWTP Dike will reduce the risk of flooding at the Town of Pe Ell WWTP by creating a barrier to flood waters that is 2 feet higher than the level that water reached in the 2007 flood event. The dike will be constructed in 2014 and will be ready to protect the WWTP in the winter of 2014-15.
Plan to ensure project	Final design of the WWTP Dike will be completed in 2013. Permits will be obtained in 2013

completion and full  
utilization of funds by  
7/01/2015:

and early 2014. Only local (City/County) permits will be required. Construction will occur in 2014.